

M-19008-BTDP 2021

Bronco® Off-Road Tubular Doors - Pull Strap/Ferrule Service Kit

NO PART OF THIS DOCUMENT MAY BE REPRODUCED WITHOUT PRIOR AGREEMENT AND WRITTEN PERMISSION OF FORD PERFORMANCE PARTS © Ford Motor Company 2020


PRIOR TO INSTALLATION READ THESE INSTRUCTION COMPETELY For questions, Call the FORD PERFORMANCE Techline 1-800-367-3788

Please visit https://www.performanceparts.ford.com for warranty information

Kit Contents

Pull Strap & Ferrule Service Kit (M-19008-BTDP)

- 1 Driver Side Ferrule
- 1 Passenger Side Ferrule
- 2 Pull Strap
- 1 I-Sheet Information Card (not shown)



Ford Factory Shop Manual purchase options <u>www.motorcraftservice.com</u>




M-19008-BTDP 2021


Bronco® Off-Road Tubular Doors - Pull Strap/Ferrule Service Kit

NO PART OF THIS DOCUMENT MAY BE REPRODUCED WITHOUT PRIOR AGREEMENT AND WRITTEN PERMISSION OF FORD PERFORMANCE PARTS © Ford Motor Company 2020

Pull Strap & Ferrule Installation Instructions

- 1. Remove door bumper.
- 2. Remove service cover plate screws.
- 3. Remove service cover plate.
- 4. Remove latch mounting fasteners.
- 5. Remove latch assembly.
- 6. Remove ferrule and pull strap from latch assembly.
- 7. Install ferrule and pull strap on new latch assembly.
- 8. Insert pull strap through latch enclosure hole, align latch to mounting holes, and install latch mounting fasteners. *Note: Torque bolts to 8.9 lb-ft (12Nm).*
- 9. Install service cover plate and fasteners.
 - *Note:* Torque bolts to 1.8 lb-ft (2.5Nm).
- 10. Install bumper assuring the marks are aligned.





Ford Factory Shop Manual purchase options www.motorcraftservice.com